


Replacing the square style Hill Billy Potentiometer – GSP100835

Equipment Needed:- flat/cross headed screwdriver, 1.5mm Allen (Hex) key, 13mm spanner

In order to change the potentiometer (pot) on your Hill Billy you will need to carry out the following instructions

1. Remove the green cap by undoing the Allen key on the side, this needs to be loosened not fully removed. Once the green cap has been removed you will need to undo and remove the nut you have now exposed.
2. Remove all the screws in the top half of the handle and remove the top part of the handle
3. Remove the Pot from its location inside the handle.
4. Depending on the age and type of your trolley, you may have a pot with wires or a connector block. You will notice three wires going into the Pot, at this stage it may be helpful to take a digital photograph of the wire sequence or jot it down.
5. It doesn't matter which type of pot you remove, wires or block, you will be supplied with the block type as a replacement. Make sure you fit it in the same way as the photograph below.



6. Fit the wires into the new pot, looking from behind with the connector block down, the wires are, left to right, Red, Blue and Green.
7. Put the pot back into its place inside of the handle as shown above, it will only go in one way!!

GolfStream Limited, Lakesview Business Park, Canterbury, Kent. CT3 4JH

Telephone: 01227 713173

Fax: 01227 719884

E-Mail: sales@golfstream.co.uk

Website: www.golfstream.co.uk



8. Replace all the screws and tighten being careful not to trap any wires between the upper and lower handle.
9. Put the green cap onto the newly fitted Pot and tighten with the Allen key, do not over tighten.
10. Test with a quick 9!

GolfStream Limited, Lakesview Business Park, Canterbury, Kent. CT3 4JH

Telephone: 01227 713173

Fax: 01227 719884

E-Mail: sales@golfstream.co.uk

Website: www.golfstream.co.uk